

# **2025 STANDARD DETAILS**

# Summary of Changes

### **INDEX OF SHEETS**

1. Added BICYCLE SHARED LANE DETAILS D-909.

### **D-100 GENERAL NOTES**

1. Deleted note 48. THE QUANTITY FOR THE CURB AND GUTTER BID ITEMS DOES NOT INCLUDE THE TRANSITION AT THE INLETS. THE TRANSITIONS ARE SUBSIDIARY TO THE CURB AND GUTTER BID ITEMS.

#### D-101 STR. SECTION, JOINT LAYOUT, MONUMENT BOX

- 1. Removed 2" Asphalt from the Monument Box Detail.
- 2. Revised the width of the Manhole In Payed Area Detail to be 4'-0" instead of 6'-0".

## D-300 STORM SEWER INLETS

1. Deleted note 10. THE THROAT AND TRANSITION ARE SUBSIDIARY TO STRUCTURE.

#### D-901 PAVEMENT MARKING DETAILS 2

1. Revised the 4" Solid White Double Channelization to 6" Solid White Channelization for the TYPICAL LEFT TURN CHANNELIZATION ISLAND LANE MARKINGS Detail.